

Little Squalicum Park Temporary Trail Closure

Map Legend

- Trail Closed Until Construction Is Complete
- Intermittent Closures for Construction Access

For more information, contact:
 City of Bellingham
 Parks and Recreation
 Design and Development Division
 360-778-7000



Portions of Little Squalicum Park contain contamination that requires cleanup under the criteria established under the *Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)*.

The US Environmental Protection Agency (EPA) will be overseeing a removal action of this contaminated material by implementing a cleanup action. The cleanup action proposed by the EPA includes rerouting Little Squalicum Creek into the historic creek channel located just southeast of the creek's current location. Additional activities include excavating contaminated material, placing that contaminated material into a repository onsite, and covering the contaminated material with geotextile fabric and soil.

Construction of the cleanup action is expected to begin in August and be completed within 2 months. During this time, portions of the trail through the Park will be closed to the public.

For more information, go to the EPA's website at: <http://go.usa.gov/ltk> and go to the Oeser Company Web page under Little Squalicum Creek.



Note	Location	MUTCD ³	Sign	Arrow Direction	Size
1	W. Illinois Street / Bay to Baker Trail	Custom	Trail Detour Map	None	24x36
1	Trail from BTC	Custom	Trail Detour Map	None	24x36
1	Lindbergh Avenue	Custom	Trail Closure Map	None	24x36
1	Little Squalicum Beach	Custom	Trail Closure Map	None	24x36
1	All trail entrances from Marine Drive Trailhead	Custom	Trail Closure Map	None	24x36
2	W. Illinois Street / Bay to Baker Trail	R9-9	"Trail Closed Ahead"	None	24x12
2	All trail entrances from Marine Drive Trailhead	R9-9	"Trail Closed Ahead"	None	24x12
3	Trail from BTC	R9-9	"Trail Closed"	None	24x12
3	Lindbergh Avenue	R9-9	"Trail Closed"	None	24x12
3	Little Squalicum Beach	R9-9	"Trail Closed"	None	24x12

Notes:

1. Signs to be mounted on steel post in accordance with PW and MUTCD standards.
2. Utility locate shall be completed before signs are installed.
3. MUTCD reference is included for standard size, color and symbols. Wording and arrows may vary as stated in the table above.



**TRAIL
CLOSURE
MAP**



R9-9



R9-9